CHITALDROOG DIVISION.

ADVERTISEMENT.

The 23rd March 1893.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Chitaldroog Division, up to 10th April 1893, for constructing a new Taluk Cutcherry at Challakere. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1895.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Chitaldroog, between the hours of 11 A. M. and 5 P. M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed :—

Description of Work.	Per.	Quantity.
Stone in chunam	C. Ft.	12,258
Brick in chunam	Do	20,020
Slab stone work	Do	483
Arch work (Brick in chunam)	Do	468
Cornice work	R. Ft.	1,128
Plastering with chunam	Sq.	269·32
White washing	Do	144·71
Color washing	Do	124·61
Roofing with Mangalore tiles, teak reepers, &c.	Do	70·24
Flat Terrace roofing	Do	1·56
Bengal Terrace	Do	13·32
Concrete, Flooring including plastering	Do	41·88
Gravel flooring	C. Yds.	8
Wood work teak	C. Ft.	542
Earthwork foundation excavation	Do	522
Filling in basement	L. S. Rs.	..
Iron (wrought)	lbs.	373
Painting (chocolate)	Sq.	28·74
Wood-oiling two coats	Do	41·48
Bamboo matting	Do	28·87
Door to Treasury room 3′ × 6′ with iron, &c.	Each.	1
Door, small, 3′ × 6′ pannelled	Do	17
Do 3′ × 6′ battened	Do	5
Do large, 5′ × 6′ do	Do	1
Windows, large, 3′ × 3½′ iron bars, &c.	Do	16
Do ventilators 3½′ × 1½′ do	Do	2
Do pannelled 3′ × 3½′ do	Do	10
Do battened with iron bars 3′ × 1½′	Do	7
Do do 2′ × 1½′	Do	9
Brick in chunam	C. Ft.	23
Flaging	Sq.	340
Ornamental cornice	R. Ft.	54
Date stone	L. S.	..
Gate with iron work, complete	Do	..
Ornamental finials	No.	5
Ornamental stone pillars at the entrance	Do	8
Wooden screen	L. S.	..
Wooden railings	Do	..
Drainages, &c.	Do	..
Zinc gutters at valleys	R. Ft.	60

4. Each tender must be accompanied by a deposit of Rs. 100 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing a new Taluk Cutcherry at Challakere", in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within 8 days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond ; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

D. RANGA RAO,
Offg. Executive Engineer.